



*May 7, 2024*

*Ben Estes*

*Estimate*

*Subject: Stone work on the edge of the pavement at the tennis courts in Irvington, approximately 300 linear feet.*

*Project: (1)The grass and dirt/mud will be dug out and hauled away.*

*(2)The edge will be built up to grade using #26 blue crushed stone at a width of 4 to 5 feet and to not fill in the existing ditch/ swaled area.*

*(3)The filled area will be covered with a thin layer of #57blue crushed stone.*

*\$4,000.00*

*Sincerely,*

A handwritten signature in cursive script that reads "Dan Thomas Brown".

*Dan Thomas Brown, Pres.  
Earth Resources, Inc.*

RIPRAP AND EXCAVATION

P.O. Box 520, LANCASTER, VA 22503  
(804)435-1085, FAX (804)435-2906